



2267-2

#### Joint ITER-IAEA-ICTP Advanced Workshop on Fusion and Plasma Physics


3 - 14 October 2011

The ITER Project

#### SNIPES Joseph Allan

ITER Organization, Directorate for Plasma Operation Plasma Operations Group, POP, Science Division Building 523/023, Route de Vinon sur Verdon 13115 St Paul lez Durance FRANCE

# The ITER Project



ITER Organization
13115 St. Paul-lez-Durance, France


The views and opinions expressed herein do not necessarily reflect those of the ITER Organization.



## **Outline**

- ➤ ITER Project Overview
  - What is ITER?
  - ITER Management Structure
- Progress in Design and Construction
  - ITER schedule
  - Design nearing completion
  - Major components under construction
  - Building status
- **Conclusions**

ITER - A Unique Scientific, Technological and



# ITER Scope - Mission Goals

### **Physics:**

- ITER is designed to produce a plasma dominated by  $\alpha$ -particle heating
- produce a significant fusion power amplification factor (Q ≥ 10) in long-pulse operation
- aim to achieve steady-state operation of a tokamak (Q = 5)
- retain the possibility of exploring 'controlled ignition' (Q ≥ 30)

## **Technology:**

- demonstrate integrated operation of technologies for a fusion power plant
- test components required for a fusion power plant
- test concepts for a tritium breeding module


# ITER Overall Project Cost (OPC)

- The cap on the total cost for the Construction Phase approved in July 2010 is 4700 klUA
- Table shows the total cost over the lifetime of the project:

Construction Phase	4584.7 kIUA	
Additional Resources	115.3 kIUA	
Operation Phase	188 kIUA per year	
Deactivation Phase	EUR 281 Million	
Decommissioning Phase	EUR 530 Million	

NB: 1 kIUA = 1 M \$US (1989) = 1.58 M Euro (2011)

# ITER Tokamak - Major Components



### **ITER Organization Structure**

**Financial Audit Board** 

Management **Advisory Committee** 

ITER Council **Science and Technology Advisory Committee** 

**Test Blanket Module Program Committee** 

#### Office of the Director-General

Director: Takayuki Shirao

- · IO Strategic Planning
- External Relations
- Communication
- Others

**ITER Council Secretariat** 

Internal Audit Service

**Legal Affairs** 



Osamu Motojima Director-General

### **Project Board**

### **Bureau of International Cooperation**

Head: DDG

DDG

Richard

Hawryluk





DDG

Yong

Kim

-Hwan

Valery Chuyanov



DDG Dhiraj

Bora

**IO-DA** Coordination

### Domestic Agencies

- China
- · EU
- India
- Japan
- Korea
- Russia
- USA

#### **Department for** Administration DDG & Director:

Richard Hawryluk



**Department for ITER Project** 

DDG & Director: Remmelt Haange

Chief Scientist: Valery Chuyanov



#### **Department for Safety Quality & Security**

- · Health & Safety Control
- Nuclear Safety & Analysis
- **Quality Assurance**





#### **Directorate for** General Administration

Director Jin Ju

- Human Resources
- Procurement & Contract
- Document Control
- General Services

#### **Directorate for** Finance, Budget & Control

Director (acting) Richard Hawryluk

- Finance & Budget
- Project Management
- **Project Information** System

#### **Directorate for** Plasma **Operation**

Director **David Campbell** 

- Science
- Technology

#### Directorate for **Tokamak**

Director (acting) Remmelt Haange

- Magnet
- Vessel
- Internal Components

#### **Directorate for** Central **Engineering & Plant**

Director Yong-Hwan Kim

- Electrical Engineering
- Fuel Cvcle Engineering
- Plant Engineering

#### **Directorate for** CODAC. Heating & Diagnostics

Director Dhiraj Bora

- Control System
- Diagnostics Heating and **Current Drive**

#### **Directorate for Buildings & Site** Infrastructure

Director **Timothy Watson** 

- **Building System**
- Site Management & Logistics
- **Nuclear Buildings**
- Non-Nuclear **Buildings**


#### **Directorate for** Central Integration & Engineering

Director Mitsunori Kondoh

- Assembly and Operations
- · CAD & Design Coordination
- Technical Integration

### **Human Resources**

- As of end May 2011, the IO has <u>a total of 475 staff</u> members with 305 professional and 170 technical support staff members;
- Since January, the IO has posted 20 positions, and 220 applications have been received. 11 staff members' employment contracts started (9 Professional staff, 2 technical support staff) while 10 persons left the IO. With the foreseen recruitments and departures, the total staff number will be 494 by the end of 2011.



	Professional staff	Support staff	Total
CN	16	4	20
EU	185	125	310
IN	12	16	28
JA	26	7	33
КО	21	5	26
RU	19	3	22
US	26	10	36
Total	305	170	475

P Staff Distribution by Members


# The ITER Project Team - Domestic Agencies




 90% of ITER components will be supplied "in-kind" by the Members through their Domestic Agencies

# **Progress on ITER Design and Construction**

## **Present ITER Construction Schedule**




# **Plant Systems Configuration Models**




## Status of Procurement Arrangements (PAs)

- > The IO and relevant Domestic Agencies have signed <u>55 PAs</u>, amounting to a total of over<u>€3000M</u>, representing 70% of the total procurement value for the construction of ITER;
- > PAs are prioritized according to the Integrated Project Schedule (IPS); approximately 20 more PAs are scheduled to be signed by the end of 2011;
- ➤ Additional Direct Investment (ADI) for project changes that have been accepted into the Baseline total €16M
- > These were added to the Overall Project Cost (OPC) as approved at the Extraordinary Meeting of the ITER Council (IC-Ex) in July 2010

# **Cryostat Status**




- Provides the vacuum insulation for operating the superconducting magnets and thermal shield system
- 304L Stainless steel 40 180 mm thick
- Weight ~3500 tonnes




IN-DA signed PA September 2011

## **Vacuum Vessel Status**





- 19.4m outer diameter, 11.3m height, 5300 tonnes
- provides primary tritium confinement barrier
- VV sector and port PAs signed (EU, KO, IN, & RF)
- KO VV & port contract awarded to Hyundai Heavy Industries
- Manufacturing schedule is on the critical path!!




Page 15

### Large Scale Mock-Ups of Vacuum Vessel and Thermal Shield




Inboard segment of a VV sector






Korean Domestic Agency is verifying the manufacturing design and fabrication methods **Photos: KO DA** 


## **Torus Vacuum Controlled by 5 Lower Port Cryopumps**




~10 s required to change pumping speed from 0 - 100% MAX # Pulses Pulse Length (s) 40 400 18 1000 3000


# **Magnet System**







6 PF Coils (EU & RF)




18 TF Coils (EU & JP)

48 superconducting coils

~9800 tons

~187 km of conductor 11.8 T (peak TF field) 68 kA (peak current) Stored energy: 51 GJ




31 Feeders (CN)

CS Coils – Stack of 6 (US)



## **TF Conductor Procurement**





**ITER TF Conductor** 

~90 km / 400 t of Nb<sub>3</sub>Sn conductor
 (The biggest Nb<sub>3</sub>Sn conductor procurement in history!)
 ~150000 km of strand (15 x around Earth)
 Operates at ~5 K
 11.8 T (peak TF field)
 68 kA (peak TF current)

Manufactured by EU, JA, RF, CN, KO, & US








- Signed procurement contract for TFC PA's (Toshiba is main contractor)
- Commissioning of winding machine @ Toshiba in progress
- Welding trials in progress for TFCs and TFC Case


### **Europe**

- Signed a procurement contract for prototype radial plates
- Winding Package call-for-tender underway
- Contract signed to qualify the TFC Case welds

# **Progress on TF Coils - Japan**



# **Progress on TF Coils - EU**




**CNIM** and Le Creneau


## TF & PF conductor activity underway in Heifei, China



## **TF Conductor Production**




**TF Qualification Sample Summary** 



- All TF conductor qualification samples were manufactured at CRPP and enabled supplier qualification in all 6 DAs involved in TF conductor production
- As of today, over 40% of required 450t of Nb<sub>3</sub>Sn strand has been produced around the world


TF Strand Production Dashboard




TF Strand Production Summary



# High Temperature Superconductor Lead Design




## **Poloidal Field Coil Status**




Page 26

## **In-Vessel Coils**



ITER In-Vessel Coils (IVCs): 27 ELM & 2 VS Coils




### Background

- Vertical Stability (VS) coils provide fast response for plasma vertical position control
- Uncontrolled Edge Localized Modes (ELMs) can lead to unacceptably rapid erosion of the divertor target
- ELM coils provide resonant magnetic pertubations (RMP) at plasma edge to stabilize ELMs

### **Status**

- Preliminary Design Review completed
- R&D activities on conductor and joints are in progress
- Interfaces have been fully implemented into VV design
- Decision whether to implement ELM coils must be made in 2012 in time for blanket PA

## Latest In-Vessel Coil Design



# **In-Vessel Components - Materials**

### CFC divertor targets (~50m²):


- erosion lifetime (ELMs!) and tritium codeposition
- dust production

### Be first wall (~700m²):

- dust production and hydrogen production in off-normal events
- melting during VDEs

## W-clad divertor elements $(\sim 100 \text{m}^2)$ :

- melt layer loss at ELMs and disruptions
- W dust production radiological hazard in by-pass event



# **In-Vessel Components - Materials**

### • CFC divertor targets (~50m<sup>2</sup>):


- erosion lifetime (ELMs!) and tritium codeposition
- dust production

### • Be first wall (~700m<sup>2</sup>):


- dust production and hydrogen production in off-normal events
- melting during VDEs

### W-clad divertor elements (~100m²):

- melt layer loss at ELMs and disruptions
- W dust production radiological hazard in by-pass event




# In-Vessel Components - Blanket/ First Wall



## **Blanket Shield Module Status**


- 440 blanket modules
- 18 poloidally
- 18 or 36 toroidally
- Mass: 1530 tons







**Shield Module** 

- Conceptual design complete for several standard modules
- Mock ups provided by US, EU, RF, KO, CN and JP
- Nearing completion of the formal test program - 12,000 normal cycles at 0.875MW/m2 and 1000 MARFE cycles at 1.4MW/m2





**First Wall Panel** 




Mock-ups




## **Test Blanket Systems in ITER**

- ♦ 3 ITER equatorial ports devoted to tritium breeding test blanket modules (TBMs)
- ◆ Each TBM is half-port size → 6 TBMs to test different tritium breeding technologies



Page 33

# **Divertor Status**







- Four of five PA's Signed
- Initiating all-tungsten design




### **Qualification Prototypes**

- All the 3 Domestic Agencies have qualified
- Pre-PA Qualification process successfully completed in all the concerned

DAs.




# ITER Cooling Water Systems (CWS)



Cooling Water System: Removes heat from components and rejects heat to the environment

**Cryogenic System** 



Cools down the superconducting magnets, cryopumps, and thermal shield

# **Tritium Handling**

- Handling of D and T involves techniques typical in gas processing
  - Hydrogen isotopes are gaseous under normal conditions
    - H<sub>2</sub>, D<sub>2</sub> and T<sub>2</sub> are colourless, odourless and tasteless
  - ITER Pellet Injection works with solid deuterium and tritium ice
    - Melting points of D<sub>2</sub>, T<sub>2</sub> are 18.7K (-254.4°C) and 20.6K (-252.5°C), respectively
  - Tritium Plant Isotope Separation Systems distills liquid hydrogen
- Pumps, pipe work, valves, instruments must be "tritium compatible"
  - Leak tight to highest standards (individual leak rates < 10<sup>-10</sup> Pam<sup>3</sup>s<sup>-1</sup>)
    - Deuterium and Tritium should neither be trapped nor should they leak out
      - Economical and ecological incentives
  - Only metals or ceramics in direct contact with tritium
    - Organic materials (polymers, etc.) degrade due to beta radiation
- 4kg of tritium will be held on ITER site

### **Tritium Plant**

#### Tritium plant processes tritium for the tokamak and plant systems


- 7 Stories
  - 2 below grade
- L = 80 m
- W = 25 m
- H = 35 m

T site inventory: < 4 kg

Plasma T throughput: ~ 1 kg/h


Plasma T inventory: ~ 0.2 g

T release limit < 0.6 g/year




### **Remote Handling**


#### Must handle 4.5 ton blanket modules and 9 ton divertor cassettes




Blanket RH System (JA)




Transfer Cask Systems (EU+CN)




**Multi Purpose Deployer** 



**Hot Cell RH Equipment** 



**Cassette Toroidal Mover** 




In-Vessel Viewing System

# **Development of Negative-Neutral Beam Injection Systems Is Ongoing**


100kV ion source test bed (begin 2014)

full size HNB injector test bed (end 2016)



Neutral beam test facility being built in Padova, Italy to perform full-scale tests of 1 MeV negative ion neutral beam technology

### Good Progress in Gyrotron Development for Electron Cyclotron Heating & CD System




- 170 GHz EC system
- Transmit up to 20 MW from 1 equatorial and 4 upper launchers
- Total of 24 gyrotrons rated to 1 MW can be steered to any of the 5 launchers


### Ion Cyclotron Heating & CD System

- Two antennae (equatorial port plugs) (EU)
- Transmission and matching systems (US)

- RF sources (8x3MW + 1 spare, 40-55MHz, for 20MW in plasma) (IN)



# **Itinerary of ITER Components**




# **Site Construction Progress**


- Construction of the Tokamak Complex is underway
- > The Hot Cell building and Assembly Hall excavation and the concrete seismic basemat are complete
- > The construction of the ITER Headquarters main office building is progressing well with completion scheduled for late summer 2012
- The PF coil building is nearly complete. The building is expected to be finished by the end of 2011
- Réseau de Transport d'Electricité installation of the 400 kV substation to power ITER is underway




### **ITER Site in September 2011**



### **ITER Site after Construction**



# **Plan View of ITER Site**



### **Construction of the Tokamak Complex**



#### **Construction of the ITER Head Quarters**



#### **Construction of the Poloidal Field Winding Building**



#### Construction of the 400 kV Substation



#### **Conclusions**

#### > The ITER Project is rapidly evolving

- 7 International Parties → 475 staff working together as a Team
- Building a 500 MW long pulse burning plasma experiment
- Contracts already signed for 70% of construction procurement value
- Vacuum vessel construction is underway in Korea
- TF superconductor production underway in EU, JA, RF, CN, KO, US

#### Designs progressing on

- In-vessel coils
- Blanket shield modules
- Tungsten divertor

#### Building construction on site progressing for

- PF coil building to be complete at the end of this year
- Main office building to be complete fall 2012
- Tokamak complex finishing seismic basemat