



The  
University  
Of  
Sheffield.

**NucleUS**  
Immobilisation Science Laboratory

# Status of the Fukushima Dai-ichi NPP and our contribution to its decommissioning

**Neil Hyatt\***

Department of Materials Science & Engineering,  
University of Sheffield, UK

**ICTP Summer School on Radiation Effects on Nuclear Wasteforms**  
11-16 September 2016

*The views expressed in this talk are the personal opinion of the speaker  
and do not necessarily reflect those of sponsors or funding agencies*



@ISL\_Sheffield

# Fukushima Dai-ichi site before March 2011



© Reuters





The  
University  
Of  
Sheffield.

# Fukushima Dai-ichi site March 2011



Image credit: Xinhua/AFP





The  
University  
Of  
Sheffield.

# Fukushima Dai-ichi site March 2016




Image credit: Japan Times / KYODO





# Fukushima Dai-ichi site plan






# Status of Fukushima Dai-ichi Units 1-4

**All Units continue to be in cold shutdown**


※ **Cooling water injection**



Values as of 11:00 on 29th January 2016

	RPV bottom temp.	PCV internal temp.	Fuel pool temp.	Water injection to the reactor
Unit 1	~15°C	~16°C	~13°C	4.5m <sup>3</sup> / h
Unit 2	~20°C	~21°C	~29°C	4.3m <sup>3</sup> / h
Unit 3	~18°C	~18°C	~19°C	4.3m <sup>3</sup> / h
Unit 4	No fuel, so monitoring not required	No fuel, so monitoring not required	~8°C	—

Plant parameters, including RPV and PCV temperatures, are monitored continuously 24 hours a day.



**<Cooling multiplexed>**

Various auxiliary means have been readied to inject cooling water into the core to maintain Units 1~3 in cold shutdown









Even if power sources fail, cooling water injection can be restarted using fire engines within three hours.

Also, multiplexing is achieved with multiple tanks ready to serve as sources for cooling water injection pumps.




# Status of Fukushima Dai-ichi Units 1-4

**Common priority : strategy for fuel / debris removal for seismic and worker safety**

Unit 1	<div>Current status</div> <div>Tasks</div>	<p><b>Building cover installed</b> October 2011  <b>Removal of building cover to allow removal of fuel from spent fuel pool</b></p> <p>Identification of debris on operating floor and inside spent fuel pool  Countermeasures for dispersion of radioactive materials during removal of building cover</p>	<p>Immediately after the earthquake</p>  <p>Now</p> 
Unit 2	<div>Current status</div> <div>Tasks</div>	<p><b>Blow out panel closed</b>  <b>Very high dose rate inside building</b></p> <p>Radiation dose reduction measures</p>	<p>Immediately after the earthquake</p>  <p>Now</p> 
Unit 3	<div>Current status</div> <div>Tasks</div>	<p><b>Debris removal from top of the reactor building competed</b> October 2013  <b>Installation of fuel removal cover and fuel handling facility planned</b></p> <p>Radiation dose reduction measures  Installation of remote controlled heavy machinery</p>	<p>Immediately after the earthquake</p>  <p>Now</p> 
Unit 4	<div>Current status</div>	<p><b>Fuel removal from spent fuel pond completed</b>  Start: 18 Nov. 2013, finish 22 Dec. 2014</p>	<p>Immediately after the earthquake</p>  <p>Now</p> 

# Fukushima Dai-ichi site decommissioning plan


## Roadmap Targets (formulated Dec. 2011, revised Jun. 2013 and Jun. 2015)



## Fuel debris removal (Unit 1, 2 and 3)

In terms of reducing radiation exposure during work process, the most reliable method of fuel debris removal is to remove the fuel debris while submerged. But depending on the results of future investigations, we may adopt a substitute method of such as taking fuel debris without filling the primary containment vessel with water.

Construction method for fuel debris removal (image)




## Spent fuel removal plan (Unit 1, 2 and 3)


FY	2015	2016	2017	2018	2019	2020	2021	2022
Unit 1	Demolition building covers		Removal rubbles		Installation covers		Spent fuels removal	
Unit 2	Demolition upper buildings			Plan①	Installation containers		Spent fuels removal	
	Preparation	Removal rubbles	Plan②		Installation covers			
Unit 3	Installation building covers			Spent fuels removal				



Frame for Unit 1 pool



Cover for Unit 3 pool



Equipment for Unit 2

To facilitate the removal of fuel assemblies and debris in the Unit 2 spent fuel pool, we decided to dismantle the whole rooftop above the highest floor of the Reactor Building.



# Reactor cooling and water decontamination

- Water to cool fuel molten during the accident and groundwater have mixed, generating approximately 300 tons of contaminated water per day. Countermeasures are being implemented based on the following three basic policies.

## Policy 1. Remove source of contamination



- Clean up contaminated water with Multi-nuclide removal equipment (ALPS)
- Remove contaminated water in trenches (Underground tunnel with piping)

## Policy 2. Isolating groundwater from contamination sources


- Pumping up groundwater through groundwater bypasses
- Pumping up groundwater through wells near buildings
- Installation of frozen-soil impermeable wall on the land side
- Paving of site to curb permeation of rainwater into soil

## Policy 3. Preventing leakage of contaminated water

- Ground improved with water glass
- Installation of impermeable walls on the sea side
- Augmentation of tanks (replacement with welded tanks, etc.)




# Management of contaminated water




## Emergency Measure ① To remove highly contaminated water in trenches

## To remove contamination source



- Highly contaminated water from immediately after accident remains in underground tunnels (trenches) on sea side of buildings
- Highly contaminated water, which poses a risk of infiltrating or spreading into surrounding area, will be removed (Finished removing the water - Unit 2; June 2015, Unit 3; July 2015, Unit 4; December 2015)

## Emergency Measure ② To pump up groundwater on mountain side of buildings (groundwater bypass)



## Temporary storage tank analysis results (collected on Feb. 24)

	Cesium 134	Cesium 137	Total Beta radiation	Tritium
TEPCO	ND (0.66)	ND (0.60)	ND (0.92)	180
Third-party agency	ND (0.59)	ND (0.55)	ND (0.53)	170
TEPCO's limit	1	1	5	1,500
Legally notifiable limit	60	90	-	60,000
WHO drinking water quality guideline	10	10	-	10,000

•TEPCO; Tokyo Electric Power Company

•ND indicates "not detectable" (below the limit of detection, which is stated in parentheses)


## To control increase in contaminated water



- Groundwater inflow into the buildings is reduced by pumping up and bypassing groundwater, flowing from the land side, on the upstream side of the buildings.
- Start of water drainage on May 21, 2014.

## Emergency Measure ③ To improve foundation of contamination area, pump up groundwater, pave surface

## To prevent outflow into port




- Chemical grouting will be used to improve the foundation and control outflow of contaminated groundwater
- To inhibit infiltration of rainwater, surface will be paved with asphalt or other material







# Management of contaminated water



## Fundamental Measure② Install land-side (frozen soil) impermeable wall


To control increase in contaminated water and prevent its flow into port



- Buildings will be enclosed by ice wall to curb inflow of groundwater into buildings
- Full-scale construction began in June 2014
- Construction of the mountain side was completed in September, 2015. As for the sea side, freeze pipe etc. setting construction was completed in January, 2016

## Fundamental Measure ① Construct sea-side impermeable wall


To prevent flow out into sea



- Impermeable wall will be constructed along the sea side of Units 1~4 to prevent outflow of contaminated groundwater into sea
- Construction of steel sheet-piles comprising impermeable wall was completed in October 2015. The radioactive material concentration inside the harbor has become lower

## Fundamental Measure ③ To pump up groundwater from sub-drains


Curb inflow of groundwater into R/B, etc.



- Wells (sub-drains) installed near buildings will be rehabilitated and groundwater around buildings will be pumped up to control inflow into the buildings
- To start pumping up groundwater and draining cleanup water from September 2015



# Reactor cooling and water decontamination









# High Dose Spent Adsorbents

## Challenges associated with High Dose Spent Adsorbents


- Several ion-specific microporous materials
- Key nuclides include:  $^{90}\text{Sr}$ ,  $^{137}\text{Cs}$ ,  $^{60}\text{Co}$
- Granular dispersible materials
- Self heating – steam production
- Radiolysis – hydrogen production
- Stress corrosion cracking – sea salt aggravated

➤ **HDSAs require waste conditioning process**




# Example: HIP conditioning of Sr-Treat<sup>®</sup> HDSEA

Cs/Sr exchanged Na titanate – HIPped without additives, i.e. 100 % waste loading  
 SPFT  $\log q/S = -7.0$ , 90 °C



**Figure 1.** Sr Treat granules with layered titanate structure (Na<sub>2</sub>Ti<sub>6</sub>O<sub>13</sub>), transformed into dense ceramic wasteform as shown by back scattered SEM. Bright areas correspond to Sr rich phases, the inhomogeneous Sr distribution reflects the different Sr uptake during ion exchange.






# Site improvements for decommissioning

- Efforts are being made to secure personnel over the long term while being sure to manage workers' radiation exposure.
- Further efforts are also being made for continuous improvement of the working environment while understanding the needs of the site.

## Changes in the number of workers

- The number of workers per weekday (employees from TEPCO and contractors) engaged in work during January is assumed to be approximately 6,460 people.
- The percentage of locally born workers is approximately 50% in Dec..



Change in the average number of workers (actual value) per weekday in the months following 2013.

## Workplace environment improvements





- Full-face mask **necessary** area
- Full-face mask or Half-covered face mask **necessary** area
- Full-face mask **unnecessary** area



## Improving the work environment

- Improving convenience
- A large rest house with a capacity of approx. 1,200 workers was established and its operation commenced on May 31, 2015.
- A new office building was constructed in 2014 allowing for smooth communication with areas close to the field.



New office building and office



Large rest house

- Fukushima Revitalization Meal Service Center
- Construction was finished on 31st March, 2015
- Providing warm meals
- Creation of employment opportunities in association with the construction and operation of the meal service center
- Dispelling of harmful rumors through the usage of Fukushima - produced cooking ingredients and the local employment.



## Ensuring stable employment over the long term

- The importance of arranging for an environment in which the people from contracting companies can work over the long term was confirmed in order to steadily move forward with decommissioning work for 40 years.
- Currently, approximately 90% of orders are fulfilled by negotiated contracts.
- By securing long term workers, more deliberate personnel assignment and human resource development is possible.



# Contamination of sea water in quay area

- The radioactive material concentration in the sea area decreased by one- 100,000th ~ 1,000,000th after the accident

