



1970-1

Signaling the Arrival of the LHC Era

8 - 13 December 2008

**Current Status of the LHC** 

Albert De Roeck CERN Switzerland

# Status of the LHC




Albert De Roeck CERN and University of Antwerp and the IPPP Durham

#### SIGNALING THE ARRIVAL OF

#### THE LHC ERA

8 - 13 December 2008

Miramare, Trieste, Italy










#### The LHC: a proton proton collider




The LHC will determine the Future course of High Energy Physics First beam in the LHC on 10/09/08!!!



#### The LHC: 22 Years Already!

#### LHC History

- 1982 : First studies for the LHC project
- 1983 : ZO/W discovered at SPS proton antiproton collider
- 1989 : Start of LEP operation (Z boson-factory)
- 1994 : Approval of the LHC by the CERN Council
- 1996 : Final decision to start the LHC construction
- 1996 : LEP operation > 80 GeV (W boson -factory)
- 2000 : Last year of LEP operation above 100 GeV
- 2002 : LEP equipment removed
- 2003 : Start of the LHC installation
- 2005 : Start of LHC hardware commissioning
- 2008 : Expected LHC commissioning with beam



1984: cms energy10-18 TeVLuminosity $10^{31}$ - $10^{33}$  cm<sup>-2</sup>s<sup>-1</sup>1987: cms energy16 TeVLuminosity $10^{33}$ - $10^{34}$  cm<sup>-2</sup>s<sup>-1</sup>Final: cms energy14 TeVLuminosity $10^{33}$ - $10^{34}$  cm<sup>-2</sup>s<sup>-1</sup>

## **Recent High Energy Colliders**

Highest energies can be reached with proton colliders

Machine	Year	Beams	Energy (√s)	Luminosity
SPPS (CERN)	1981	рр	630-900 GeV	6.10 <sup>30</sup> cm <sup>-2</sup> s <sup>-1</sup>
Tevatron (FNAL)	1987	рр	1800-2000 GeV	10 <sup>31</sup> -10 <sup>32</sup> cm <sup>-2</sup> s <sup>-1</sup>
SLC (SLAC)	1989	e⁺e⁻	90 GeV	10 <sup>30</sup> cm <sup>-2</sup> s <sup>-1</sup>
LEP (CERN)	1989	e⁺e⁻	90-200 GeV	10 <sup>31</sup> -10 <sup>32</sup> cm <sup>-2</sup> s <sup>-1</sup>
HERA (DESY)	1992	ер	300 GeV	10 <sup>31</sup> -10 <sup>32</sup> cm <sup>-2</sup> s <sup>-1</sup>
RHIC (BNL)	2000	pp / A A	200-500 GeV	10 <sup>32</sup> cm <sup>-2</sup> s <sup>-1</sup>
LHC (CERN)	2009	pp (AA)	10-14 TeV	10 <sup>33</sup> -10 <sup>34</sup> cm <sup>-2</sup> s <sup>-1</sup>
		Lur	ninosity = number of ev	ents/cross section/sec


- Limits on circular machines
  - Proton colliders: Dipole magnet strength  $\rightarrow$  superconducting magnets
  - Electron colliders: Synchrotron radiation/RF power

## LHC Physics Program

- Discover or exclude the Higgs in the mass region up to 1 TeV. Measure Higgs properties
- Discover Supersymmetric particles (if exist) up to 2-3 TeV
- Discover Extra Space Dimensions, if these are on the TeV scale, and black holes?
- Search other new phenomena (e.g. strong EWSB, new gauge bosons, Little Higgs model, Split Supersymmetry)
- Study CP violation in the B sector, B physics, new physics in B- decays
- Precision measurements of  $m_{top}$ ,  $m_W$ , anomalous couplings...
- Heavy ion collisions and search for quark gluon plasma
- QCD and diffractive (forward) physics in a new regime

5

#### Physics at the LHC: pp @ 14 TeV




The LHC will be the new collider energy frontier

#### **Requirements for a New Collider**

Example: Higgs particle production


Hadron colliders are broad-band exploratory machines

May need to study  $W_L$ - $W_L$  scattering at a cm energy of ~ 1 TeV




For L ~10<sup>34</sup>, Evts/yr = 10<sup>34</sup> 10<sup>-37</sup>.10<sup>-3</sup>.10<sup>7</sup> ~ 10 /yr !!

#### Detectors are essentially completed



Atlas & CMS construction started 9 years ago +TOTEM, LHCf, MOEDAL Now gearing up for first collisions... 8

## The Large Hadron Collider LHC



## LHC - yet another collider?

The LHC surpasses existing accelerators/colliders in 2 aspects :

The energy of the beam of 7 TeV that is achieved within the size constraints of the existing 26.7 km LEP tunnel.

LHC dipole field	8.3 T
HERA/Tevatron	~ 4 T


A factor <u>2</u> in field A factor <u>4</u> in size

The luminosity of the collider that will reach unprecedented values for a hadron machine:

LHC	pp	~ 10 <sup>34</sup> cm <sup>-2</sup> s <sup>-1</sup>	
Tevatron	pp	2×10 <sup>32</sup> cm <sup>-2</sup> s <sup>-1</sup>	A factor <u>100</u> in luminosity
SppbarS	pp	6×10 <sup>30</sup> cm <sup>-2</sup> s <sup>-1</sup>	

The combination of very high field magnets and very high beam intensities required to reach the luminosity targets makes operation of the LHC a great challenge !

#### The Accelerator Scheme



#### LHC Parameters

- Momentum at collision
- Momentum at injection
- Machine Circumference
- Revolution frequency
- Number of dipoles
- Dipole field at 450 GeV
- Dipole field at 7 TeV
- Bending radius
- Main Dipole Length

7 TeV / c 450 GeV / c 26658.883 m 11.245 kHz

1232 0.535 T 8.33 T 2803.95 m 14.3 m

### LHC Parameters

Bunch Intensity	1.15 x 10 <sup>11</sup>
Number of bunches	2808
emittance	5 x 10 <sup>-10</sup> m
β* fully squeezed	55 cm
beam size at IP	16 µm
Crossing angle	285 µrad
Bunch length	1.06 ns (7.5 cm)
Luminosity	10 <sup>34</sup> cm <sup>-2</sup> s <sup>-1</sup>
Total Beam energy	362 MJ per beam

Full list at: http://cern.ch/ab-div/Publications/LHC-DesignReport.html


## Magnets for the LHC (part of them)

		No. of Magnets	Aperture
Dipole	МВ	1232	twin
Lattice quadrupoles	MQ	392	twin
Lattice sextupoles	MS	688	single
Lattice Octupoles	MO	168	twin
Skew quad	MQS	32	twin
Arc skew sext	MSS	64	single
Tuning trim quad	ΜQΤ	160	twin
Octupole spool pieces	МСО	1232	single
Decapole spool pieces	MCD	1232	single
Sextupole corrector (b3) in MBA & MBB (spool piece corrector)	MCS	2464	single
Insertion region long trim quads	MQTLI	36	twin
Arc dipole corrector	МСВН	376	single
Arc dipole corrector	MCBV	376	single
Twin aperture separation dipole in IR (194mm). D4 Twin Aperture Separation	MBRB	About 9000 magnets of which 1232 are the cryodipoles	twin
dipole in IR(188mm). D2	MBRC	8	twin

#### The Cryodipole Magnets

•Superconducting (1.9 K) dipoles producing a field of 8.4 T – current 11,700A  $\Rightarrow\,$  2-in-1 magnet design

- Cost: ~ 0.5 million CHF each. Need 1232 of them
- Stored magnetic energy up to 1.29 GJ per sector.
- Total stored energy in magnets = 11GJ
- One dipole weighs around 34 tonnes




## Superfluid Helium

- To produce the high magnetic fields we need very high currents...
- Make use of the remarkable properties of He II

#### Superfluid helium:

- Very high thermal conductivity (3000 time high grade copper)
- Very low coefficient of viscosity... can penetrate tiny cracks, deep inside the magnet coils to absorb any generated heat.
- Very high heat capacity...stablizes small transient temperature fluctuations

## LHC is more than just dipoles...



## **Straight Sections**

The sections that deliver the beam to the experiment are straight and use room temperature magnets



#### Energy in the beam

## Comparison ...

The energy of an A380 at 700 km/hour corresponds to the energy stored in the LHC magnet system : Sufficient to heat up and melt 12 tons of Copper!!



## LHC RF system

□ The LHC RF system operates at 400 MHz.

□ It is composed of 16 superconducting cavities, 8 per beam.

Peak accelerating voltage of <u>16 MV/beam</u>.

For LEP at 104 GeV : 3600 MV/beam !




	Synchrotron radiation loss
LHC @ 7 TeV	6.7 keV /turn
LEP @ 104 <i>G</i> eV	~3 GeV /turn

The LHC beam radiates a sufficient amount of visible photons to be actually observable with a camera ! (total power ~ 0.2 W/m)


#### Complex interconnects

Many complex connections of super-conducting cable that will be buried in a cryostat once the work is finished.



## Planned Schedule (early summer 08)


#### First Beam circulating on 10/9/08



#### Some Issues Before Starting...

- Some magnets, while being tested before installation to the 7 TeV corresponding current, now seem to quench before (ie they turn from superconducting to normal state).
- Getting all magnets to work safely @ 7 TeV will be some work and was planned for the coming 08-09 winter shutdown

Start in 2008 was planned with 10 TeV



The LHC sectors were all commissioned to 5.5. TeV before first beam


That is, all but one..

## **Beam Injection on 9/10 August**



#### Layout of beam path





## **Beam Injection on 9/10 August**



#### Beam on screen at IR3 (first shot!)



		BTV - LHC. USER. ALL
Eile Tools		
9 ID IF 🕨 🚭 🕇	Aug 08 21:38:46 LH	IC - LHC   LHC - 01  🥩
Selection		LHC.BTVM.7L3.B1/Image
Device:	LHC.BTVM.6L4.B1 LHC.BTVM.6L4.B2 LHC.BTVM.7L3.B1 LHC.BTVM.7L3.B2 LHC.BTVSE.A4L6.B1 LHC.BTVSE.A4R6.B2 LHC.PTVSI A7P7 P2 4	Image     20-       15-    Cycle: LHC SC Nb: 0
Status		10-
Device:	LHC.BTVM.7L3.B1	
Status:	0K	₹ <sup>5</sup>
Mode:	ON	
Control:	REMOTE	
Setting		-5-
Basic Advanced	Expert	-10-
	200 mV	
First Lamp:	***	-15-
First Lamp: Second Lamp:	200 mV	
Second Lamp:	200 mV	
	200 mV	-20 -10 0 10 20

## Checking the machine before D-Day

#### **Polarity Errors**


In single pass (trajectory) mode, focusing errors can be located by:

launching controlled trajectory oscillations

comparing the measurement with the predictions

>> Identified a number of sign errors - some rather severe (see below) !

Example of a polarity inversion of a main quadrupole (IR7). This error would have spoiled the 10<sup>th</sup> September show – very difficult to get past such an error.



## Checking the Machine before D-Day


#### And we quenched with beam...

In the very early morning of August 9<sup>th</sup> during the first test, we provoked the first beam induced quench:

Bunch intensity <u>~4×10<sup>9</sup> p</u>, which is within the expected range.

> reduced the commissioning intensity to ~2-3×10<sup>9</sup> p.


In preparation of the 10<sup>th</sup>, a test revealed that even with ~2×10<sup>9</sup> p one can quench – but very unlikely in normal operation due to the large impact angle.




Preliminary results !

## Checking the Machine before D-Day

#### A look at the first quench : magnet perspective






## September 10th 2008




## 10/9/08

Start 9:30

10 SEP, 10:25 FIRST COMPLETE LHC ORBIT!




## September 10th 2008




### Beam goes around the full LHC


#### **First Beam Around**


Sept 10<sup>th</sup> 10:30 : two beam spots on a screen near ALICE indicate that the beam has made 1 turn.




## **Beam Halo and Splashes in CMS**















## **Beam Halo and Splashes in ATLAS**









first beam event seen in ATLAS



### ALICE and LHCb





## For the History Records

### September 10th

Despite the presence of an unbelievable crowd of people :

> 300 Journalist

□10:30 : Beam 1 around the ring (in ~ 1 hour). Beam makes ~ 3 turns.

□15:00 : Beam 2 around the ring, beam makes 3-4 turns.

□22:00 : Beam 2 circulates for hundreds of turns...




### **Circulating Beam**

### Beam 2 circulating – no RF

Evening of September 10<sup>th</sup>, after the crowds left:

Beam 2 makes hundreds of turns after some empirical correction (no RF)



39

17

### **Circulating Beam**


### Beam 2 captured by RF system

Evening/Night of September 11th

Beam captured and stored for ~ 30 minutes

Progress was very rapid and swift

Hopes were to have first collisions in ~ a week



### But then...

# Electrical transformer problem...

Late evening of Friday Sept. 12<sup>th</sup> an old LEP HV transformer in point 8 failed, leading to a stop of the cryogenics – LHC 'off'.

- TS/EL had no spare (!), but a spare CMS transformer was recuperated and installed during the weekend.
- Due to various other problems, the cryogenic system was only completely back for the Friday 19<sup>th</sup>.
- In the meantime, access and commissioning of remaining circuits wherever cryogenics conditions were OK.
- Late in the morning of Sept. 19<sup>th</sup> the last dipole circuit of sector 3-4 is commissioned to 5.5 TeV...

### Slides from H. Weninger

### Black 19th of September 😕

### Status on the morning of Sept. 19th

Beam 2 well advanced:

- Beam captured in RF system, good orbit and lifetimes of hours.
- Optics in 'reasonable' shape, preparing for refinements.

Beam 1 in same state as 10<sup>th</sup>:

First turn established, beam in for 3-4 turns.

Objectives for the weekend

- Bring beam 1 to same level as beam 2.
- Improve measurement and correction on beam 2.
- Try to circulate both beams together ...


But....

### And then came September 19<sup>th</sup> 11:18...


During the last commissioning step of main dipole circuit in sector 34, to 9.3kA :

- At 8.7kA, development of resistive zone in the dipole bus bar between Q24.R3 and the neighboring dipole.
- Most likely an electrical arc developed which punctured the helium enclosure.
- Large amounts of Helium were released into the insulating vacuum.
- Rapid pressure rise inside the LHC magnets
  - Large pressure wave travelled along the accelerator both ways.
  - Self actuating relief valves opened but could not handle all.
  - Large forces exerted on the vacuum barriers located every 2 cells.
  - These forces displaced several quadrupoles by up to ~50 cm.
  - Connections to the cryogenic line damaged in some places.
  - Beam 'vacuum' to atmospheric pressure


### Inter-connection



### Splices: quadrupole-dipole interconnect



### Damage zone



# **Cryostat Pedestal**



R. Aymar PECFA 28/11/08

### Damaged Quadrupole-Dipole Connection




R. Aymar PECFA 28/11/08

# Displacement in mm

### Displacements


Displacements status in sector 3-4 (From Q17R3 to Q33R3) ; P3 side																	
Based on measurements by TS-SU, TS-MME and AT-MCS																	
	Q17	A18	B18	C18	Q18	A19	B19	C19	Q19	A20	B20	C20	Q20	A21	B21	C21	Q21
Cryostat Cold mass	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 ?	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5
	Q21	A22	B22	C22	Q22	A23	B23	C23	023	A24	B24	C24	Q24	A25	B25	C25	Q25
Cryostat Cold mass	<2 <5	<2 <5	<2 <5	<2 <5	-7 -25	<2 -67	<2 -102	<2 -144	-187 <5	<2 -190	<2 -130	<2 -60	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5
	Q25	A26	B26	C26	Q26	A27	B27	C27	027	A28	B28	C28	Q28	A29	B29	C29	Q29
Cryostat Cold mass	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5	<2 57	<2 114	<2 150?	474 -45	-4 230	<2 189	<2 144	11 92? Vert	<2 50	<2 35	<2 <5	<2 <5
	Q29	A30	B30	C30	Q30	A31	B31	C31	Q31	A32	B32	<u>C32</u>	Q32	A33	B33	C33	Q33
Cryostat Cold mass	<2 <5	<2 <5	<2 <5	<2 <5	<2 <5	<2 19	<2 77	<2 148	188 <5	<2 140	<2 105	<2 62	5 18	<2 <5	<2 <5	<2 <5	<2 ?
>0 [mm] ?	Towards Values a Not mea Cold ma	s P4 are in mr asured ye	et acement	1	Electrica Dipole in Electrica	n short ci ally dama	ptions ircuit		Disconn	e cted	l	J					

### Repair



- Present strategy assumes treating all magnets Q19 to Q31 50 magnets out.
- May have to treat slightly further outside this zone (buckled vac. bellows)
- Nearly all the components are at CERN.
- Critical components are beam screens and short straight sections (quadrupoles).
- All magnets out by Christmas.
- Estimate (preliminary) November 08 to March 09.

### **Machine Status**



### Can it happen again?

# **Early Warning Signs**

- Following the incident, a closer look at the logged cryogenic data (temperatures and valve states) clearly indicated a heat source in the cell that was at the origin of the S34 incident:
  - The data revealed the presence of a ~ 200 nΩ resistance in that cell (before the incident): most likely the interconnect quality.
- Logged data recorded during commissioning of the 7 other sectors was checked to locate other potential problems : a hint was found in a cell of S12.
- Controlled calorimetric measurements (at different magnet currents) were started in the sectors that are still available to:
  - ✓ Localize cells with current dependent heat sources.
  - Confirm the source and localize precisely with electrical measurements.

### Summary of the Startup

#### Start-up with beam:

- · Despite totally ,crazy' conditions the beam start-up was excellent.
- The speed of progress with beam2 exceeded even our optimistic hopes.
- A lot was learned, but not enough to be sure that the rest of the early commissioning will proceed as well as the first 3 days...

#### Sector 34 incident:

- Revealed a weakness in the installation quality assurance.
- Revealed a weakness in the magnet protection system which did not cover dramatic bus-bar/interconnect incidents.
- Inspection and repair of ~ 50 magnets will take most of the shutdown.
- Improvements in the quench protection system, ready summer 2009, should provide early warning/protection against similar events.
- The final improvement of the pressure relief system requires a warm-up of all sectors.

### ????Schedule in 2009 ????

#### Next Steps foreseen in 2008



- Approx 30 days of beam to establish first collisions
- Approx 2 months elapsed
  - Given optimistic machine availability
  - Un-squeezed
  - Low intensity
- Continue commissioning
   thereafter
  - Increased intensity
  - Squeeze

F	Parameter	s	Rates in 1 and 5					
k <sub>b</sub>	Ν	β* 1,5 (m)	Luminosity (cm <sup>-2</sup> s <sup>-1</sup> )	Events/ crossing				
1 (3)	1010	11	1.1 10 <sup>27</sup>	<< 1				
4	1010	11	4.5 10 <sup>27</sup>	<< 1				
43	1010	11	5.0 10 <sup>28</sup>	<< 1				
43	4 10 <sup>10</sup>	11	8.0 10 <sup>29</sup>	<< 1				
43	4 10 <sup>10</sup>	3	2.9 10 <sup>30</sup>	0.36				
156	4 10 <sup>10</sup>	3	1.0 10 <sup>31</sup>	0.36				
156	9 10 <sup>10</sup>	3	5.4 10 <sup>31</sup>	1.8				

Unclear how the schedule will look like in 2009...

### News from December 5th

- Geneva, 5 December 2008. CERN\* today confirmed that the Large Hadron Collider (LHC) will restart in 2009. The top priority for CERN today is to provide collision data for the experiments as soon as reasonably possible," said CERN Director General Robert Aymar. "This will be in the summer of 2009".
- Detailed studies of the malfunction have allowed the LHC's engineers to identify means of preventing a similar incident from reoccurring in the future, and to design new protection systems for the machine.
- A total of 53 magnet units have to be removed from the tunnel for cleaning or repair, of these, 28 have already been brought to the surface and the first two replacement units have been installed in the tunnel. The current schedule foresees the final magnet being reinstalled by the end of March 2009, with the LHC being cold and ready for powering tests by the end of June 2009. "We have a lot of work to do over the coming months," said LHC project Leader Lyn Evans, "but we now have the roadmap, the time and the competence necessary to be ready for physics by summer.

### **Summary**

- The LHC has been completed in 2008.
  - Intial commissioning has started
- Start-of of the LHC on 10/9 was really good
  - Beam circulating for 30 minutes within days.
- However on 19/9 an unfortunate incident happened
  - An electrical resistive zone built up and led to an electric arc in the cryogenics part in one of the 8 arcs of the LHC
  - This created a rupture in the helium enclosure of the magnets
- This created considerable damage that needs to be repaired
  - The winter shutdown started earlier than planned
- As of 5/12 a new schedule has been announced
  - LHC back and starting physics program in 2009 after the shutdown
  - Multi-TeV collisions fall 2009?







#### 4th CERN-FERMILAB HADRON COLLIDER PHYSICS SUMMER SCHOOL CERN, 8-17 June 2009


The CERN-Fermilab Hadron Collider Physics schools are targeted particularly at young postdocs and senior PhD students.


#### Application deadline 21 February 2009

More information at : http://cern.ch/hcpss/ cern-fnal-school-sec@cern.ch Main topics: Electroweak and Higgs Physics LHC Accelerator Physics of heavy flavours Statistics Heavy flavours at LHC QCD and MC tools Particle detection and reconstruction Beyond the SM Trigger and data analysis The road to discovery at the LHC Heavy ion Physics









#### Local Organizing Committee

Albert De Roeck (Co-Chairman), CERN James Wells (Co-Chairman), CERN Nick Ellis, CERN Stefano Frixione, CERN and EPFL Christos Leonidopoulos, CERN Patricia Mage, CERN Andreas Morsch, CERN Tara Shears, Liverpool Thorsten Wengler, Manchester


#### International Advisory Committee Bogdan Dobrescu (Co-Chairman), Fermilab Michelangelo Mangano (Co-Chairman), CERN

Michelangelo Mangano (Co-Chairman), CERN Fabiola Gianotti, CERN, ATLAS Paul Grannis, SUNY at Stony Brook, DO Ian Hinchliffe, LBNL, ATLAS Rob Roser, Fermilab, CDF Olivier Schneider, EPFL Lausanne, LHCb Paris Sphicas, Athens and CERN, CMS Avi Yagil, University of California, San Diego, CMS


# Backup

### The LHC startup...

- Great startup on 10/9! (>300 journalists)
- ...Serious problem on 19/9 (> 2 months to fix)
- So, a bit more patience will be required.
- But LHC will come on strongly in 2009



Eg German press: Teilchenbeschleuniger ist schon kaputt



Breaking news: Tuesday 22/9 evening "No more beam untill spring 2003"

## Write-up

# Summary Report on the analysis of the 19th September 2008 incident at the LHC



#### Incident during powering

The magnet circuits in the seven other sectors of the LHC had been fully commissioned to their nominal currents (corresponding to beam energy of 5.5 TeV) before the first beam injection on 10 September 2008. For the main dipole circuit, this meant a powering in stages up to a current of 9.3 kA. The dipole circuit of sector 3-4, the last one to be commissioned, had only been powered to 7 kA prior to 10 September 2008. After the successful injection and circulation of the first beams at 0.45 TeV, commissioning of this sector up to the 5.5 TeV beam energy level was resumed as planned and according to established procedures.

On 19 September 2008 morning, the current was being ramped up to 9.3 kA in the main dipole circuit at the nominal rate of 10 A/s, when at a value of 8.7 kA, a resistive zone developed in the electrical bus in the region between dipole C24 and quadrupole Q24. No resistive voltage appeared on the dipoles of the circuit, so that the quench of any magnet can be excluded as initial event. In less than 1s, when the resistive voltage had grown to 1 V and the power converter, unable to maintain the current ramp, tripped off, the energy discharge switch opened, inserting dump resistors in the circuit to produce a fast power abort. In this sequence of events, the quench detection, power converter and energy discharge systems behaved as expected.

Summary Report on the analysis of the 19th September 2008 incident at the LHC

#### Follow-up actions (preliminary)

Two different goals, namely to prevent any other occurrence of this type of initial event, and to mitigate its consequences should it however reproduce accidentally. Precursors of the incident in sector 3-4 are being scrutinized in the electrical and calorimetric data recorded on all sectors, which remain cold, in order to spot any other problem of the same nature in the machine.

- An improvement of the quench detection system is currently tested, before being implemented.
- The relief devices on the cryostat vacuum vessels will be increased in discharge capacity and in number.
- The external anchoring of the cryostats at the locations of the vacuum barriers will be reinforced to guarantee mechanical stability.

Until now, no other interconnection resistance has been identified as above specification, but two (?) connections inside the cold masses (which have been tested successfully to 9T) have been measured higher than specified.

#### Summary Report on the analysis of the 19th September 2008 incident at the LHC




#### Sequence of events and consequences

Within the first second, an electrical arc developed and punctured the helium enclosure, leading to release of helium into the insulation vacuum of the cryostat.

The spring-loaded relief discs on the vacuum enclosure opened when the pressure exceeded atmospheric, thus relieving the helium to the tunnel. They were however unable to contain the pressure rise below the nominal 0.15 MPa absolute in the vacuum enclosures of subsector 23-25, thus resulting in large pressure forces acting on the vacuum barriers separating neighboring subsectors, which most probably damaged them. These forces displaced dipoles in the subsectors affected from their cold internal supports, and knocked the Short Straight Section cryostats housing the quadrupoles and vacuum barriers from their external support jacks at positions Q23, Q27 and Q31, in some locations breaking their anchors in the concrete floor of the tunnel. The displacement of the Short Straight Section cryostats also damaged the "jumper" connections to the cryogenic distribution line, but without rupture of the transverse vacuum barriers equipping these jumper connections, so that the insulation vacuum in the cryogenic line did not degrade.

### Main Dipole / Quadrupole Interconnection



Favored hypothesis for the S34 incident cause :

- Temperature increase due to an excessive resistance (estimate ~ 200 nΩ).
- Superconductor quenches and becomes resistive at high current (temperature increase due to the resistance).
- Up to a certain current, the Copper can take it (cooled by the He II).
- Beyond a certain current, 'run-away' of the temperature, splice opens, electrical arc ...



- Interleaved physics and commissioning
- Push number of bunches, intensity, squeeze...
  - □ 156 x 156
  - □ 3 x 10<sup>10</sup> protons per bunch
  - $\square \beta^* = 2 m.$
- Peak luminosity: ~1.2 x 10<sup>31</sup>
- Integrated: few pb<sup>-1</sup>

Expected luminosity in 2008 @ 10 TeV

Pushing the bunch intensities with 156x156 with reasonable operational efficiency another month would see 30 - 40 pb<sup>-1</sup>

### **Expectation for 2009**

- Commission high energy operation
  - Aim for 7TeV (magnets will decide)
  - 43 /156 bunch running to start (brief)
  - 75ns running
  - 25ns running
  - High 1032 cm-2 s-1 is in reach
- Mixture of
  - Operation for physics
  - Machine studies
  - Scheduled stops
  - Access, injection, ramp, squeeze etc
  - Colliding beams
  - Ion run ?

#### 5 10<sup>6</sup> seconds

#### Realistically (1 and 5)

150 days of physics Efficiency for physics 40% Peak luminosity around 10<sup>33</sup> cm<sup>-2</sup> s<sup>-1</sup>

Integrated luminosity ~ few fb<sup>-1</sup>

43

### Sector 3-4 recovery + 25/11/2008 / AT-MCS

